

BILL OF MATERIAL — SWITCHGEAR ASSEMBLY

SG-101

Drawing: E-104 Rev B · Project: synthetic example

Item #	Qty	Description	Manufacturer	Part Number	Vendor Cat #
1	1	Main Breaker, 1600 A, 38 kV	Eaton	VCP-W-1600	C440-1600-VCP
2	12	Feeder Breaker, 600 A, 5 kV	Eaton	VCP-W-600	C440-600-VCP
3	1	Bus Tie Breaker, 1200 A	Schneider	VR-1200-15	S-VR1200-15
4	4	Current Transformer 600:5	GE	CTW-600-5	GE-CTW600
5	4	Voltage Transformer 14.4 kV/120 V	GE	JVM-150-14.4	GE-JVM150
6	12	Protective Relay SEL-787	SEL	SEL-787	SEL-787-1A
7	1	Auxiliary Power Supply 125 VDC	ABB	BWR-125-50	ABB-BWR125
8	24	Control Wire 14 AWG (1000 ft)	Belden	9939-1000	BEL-9939
9	1	Annunciator Panel 16-pt	Rochester	RAN-16	ROC-RAN16
10	1	Ground Bus 1/4 x 2 x 84 in	Erico	GB-2-84	ERI-GB284

Total line items: 10 · **Approval:** J. Engineer (signed) · **Revision:** B